

Lazy Dog Substation Project

Town on Erie Board of Trustees Hearing 12/10/19



- Provides member systems reliable, affordable and responsible supply of electricity across nearly 200,000 square miles of the west
- Provides electricity to United Power
- Will operate the transmission(higher voltage) portion of Lazy Dog Substation



- Provides power to more than 250,000 residential and business customers across a 900 square mile service area
- United Power is a member distribution cooperative of Tri-State
- Landowner Lazy Dog Substation parcel
- Will operate distribution (lower voltage) portion of Lazy Dog Substation

Lazy Dog Substation

- New electric substation
 - Located near southwest corner of the intersection of WCR 6 and WCR 7
- 8-acre parcel owned by United Power
 - Subdivided from larger parcel, purchased from Town of Erie
- Connects to existing WAPA-owned and operated transmission line to the south



Site Location

- Vacant grassland
- Proximity to the load center where the electric power will be delivered to consumers
- Land use and zoning categories for essential public services, including electrical substations
- Compatible with surrounding uses
 - Landfill (west and south)
 - Crestone facility (north across WCR 6)
- Passive use
 - Unstaffed and minimal traffic
 - Lighting only for maintenance or emergency



Purpose, Need, and Benefit



- Steps down voltage of electricity from high-voltage transmission lines to deliver lower-voltage power via distribution lines to homes and businesses
- Adds capacity to deliver reliable, safe electric power to residential and business customers in the Town of Erie and surrounding area
- Provides backup to United Power's Parkway and Dacono substations
- Includes a wall and landscaping that provide screening



Landscaping and Screening

- Landscaping on 36% of site
 - Exceeds Town requirement for total landscaped area
- 45 trees, 247 shrubs
 - Mix of deciduous and evergreen for year-round interest
 - Meets Town requirements
- Native grass seed
- Screen wall

ALLAN BLOCK (AB) FENCE SYSTEM

FENCE BLOCK COLORS



WALL MATERIAL: CONCRETE COLOR: 385 COLUMN AND BAND MATERIAL: CONCRETE COLOR: 386

PLANT LEGEND

	1 2/11					
-	SYMBOL	QUANTITY	BOTANICAL NAME	COMMON NAME	SIZE	NOTE
	DECIDUOUS TREES					
•)	COC	5	CEL'IS OCCIDENTALIS	WESTERN HACKBERRY	2.5" CAL	B&B
	GDI	5	GYNMOCLADUS DIOICUS	KENTUCKY COFFEETREE	2.5" CAL	B&B
	TOTAL:	10	•	· · · · · · · · · · · · · · · · · · ·		
P	EVERGREEN TREES					
	PPO	35	PINUS NIGRA	AUSTRIAN PINE	6'	B&B
r	TOTAL:	35				
	DECIDUOUS	SHRUBS				
	CNA	23	CHRYSOTHAMNUS NAUSEOSUS	RABBITBRUSH	#5	
	PAM	31	PRUNUS AMERICANA	AMERICAN PLUM	#5	
	RTR	131	RHUS TRILOBATA	THREE-LEAF SUMAC	#5	
	TOTAL:	185				
	EVERGREEN SHRUBS					
	JSC	62	JUNIPERUS SCOPULORUM	ROCKY MOUNTAIN JUNIPER	#5	
	TOTAL:	62				

WS6	Examples of what these plants look like, work with Lori
	Wiedmeyer, Stephanie, 11/25/2019



Photo Simulation: WCR 6 & WCR 7, looking southwest



Landscape material illustrated in the simulated condition photo depicts 5 years growth from the time of installation.



Photo Simulation: WCR 7 south of WCR 6, looking northwest



Landscape material illustrated in the simulated condition photo depicts 5 years growth from the time of installation.

Construction

- Approximately 4.5 months from contractor mobilization to energization
- Traffic Routes as outlined in Construction Logistics Plan
 - From the North I-25, Erie Parkway, Weld County Road 7
 - From the South I-25, Highway 7, Weld County Road 7
- Applicant contact during construction
 - Tri-State Project Manager, 303-254-3408
 - In case of emergency, contact Weld County Sherriff
- No traffic and little activity after completion of construction



Permitting and Public Outreach

- February 2018: started working with Town
- Multiple coordination meetings to review landscape and screen wall requirements
- Submitted three permit applications: Minor Subdivision, Special Review Use, Site Plan
- Neighborhood meeting held in April 2019
 - Mailed invite to neighbors within 500 feet of Substation parcel line and parcel to east parcel line
 - Posted signs along Weld County Roads 6 and 7
 - 1 public attendee, HOA representative for Ranch Eggs Estates and Leisure Living neighborhoods



Project Next Steps

- Next Steps:
 - Pending permit approvals, construction start late January, 2020
 - Project in-service late May, 2020 providing reliable electric service to the Town of Erie and surrounding area



Questions?



