



ALL PURCHASE ORDERS, CONTRACTS, AND
CHECKS TO BE MADE OUT TO:
ROCKY MOUNTAIN RECREATION INC.
P.O. BOX 620411
LITTLETON, CO 80162
303-783-1452 800-636-0199

PROPOSAL

September 21, 2021
DATE

CONTACT: Luke Bolinger
PHONE: 303.926.2796
EMAIL: lbolinger@erieco.gov

SHIP TO: Luke Bolinger, Town of Erie
645 Holbrook Street
Erie, CO 80516

BILL TO: Same as above


Delano, MN
F.O.B.
FREIGHT ☒ Prepaid ☐ Collect

50% Down, Remaining due upon delivery
1.5% Monthly Finance Charge Thereafter
TERMS (Subject to Credit Approval by RMR)

Must ship by December 31st and be stored by others
until installation; vault will ship in 2022
SHIPPING TIME

October 10, 2021
PROPOSAL GOOD UNTIL

We are pleased to submit this proposal to supply the following items:

QTY	DESCRIPTION	EXTENDED AMT
		
	Mechanical and Equipment Splash Pad Package based on Design 1154291-01-01 to Include:	\$ 247,457.00
Water Play Features		
1	AquaFlier	
1	BloomBurst Set	
1	Canopy Cluster w/Acrylic	
1	FloraSpout	
1	FloraSwirl	
1	LeafCrown	
1	Tot Size WellSpring w/Acrylic	
1	VaporArc w/Acrylic	
1	WhirlPad Mushroom	
3	Arch Jet - SS	
1	Bubbler- SS	
2	Crown Jet- SS	
2	Jr. Water jewel - SS	
2	Mini Pillar- SS	
2	Sea Crawler- SS	
4	Stream Jet - SS	
2	Stream Jet Triangle- SS	
2	Triple Arch Jet - SS	

3	3" Interchangeable Mounting Stand- SS
3	4" Interchangeable Mounting Stand- SS
3	6" Interchangeable Mounting Stand- SS
1	8" Interchangeable Mounting Stand- SS
10	Winter covers for mounting stands
Mechanical Components	
Recirculation System, Sand Filtration Skid, Chemical Treatment, UV Disinfection System, Feature Skid, Distribution Manifold, Pre-fabricated Water Reservoir, Aquavator, Control Panel - On/Off, Collector Box (2), Rain Diverting Waste Valve Box	
Sequencing Upgrade	
Random sequencing upgrade to allow features to turn on and off independently. Upgrade includes the addition of electric solenoid valves on each of the feature supply lines and individual timers to interface with each solenoid valve. Valves to be preplumbed and prewired on above distribution manifold.	
System Startup and Training	
Aquatix by Landscape Structures to provide 1 factory direct technician for 2 days of system startup, balancing, and owner training. Aquatix requires 2-4 weeks advance notice depending on seasonal demand.	

Comments: Please provide a copy of your tax exempt certificate to avoid applicable charges.

ACCEPTED BY CUSTOMER	DATE	SUBTOTAL MATERIALS	\$247,457.00
		INSTALLATION	Not Included
		CONCRETE INSTALLATION	Not Included
PRINT NAME		FREIGHT	\$13,257.00
<i>Leslie Amico</i>	9/21/21	SALES TAX	Not Included
PROPOSED BY RMR REPRESENTATIVE	DATE	TOTAL	\$260,714.00
Leslie Amico			
PRINT NAME			

Additional Clarifications

- Stamped & sealed shop drawings not included in this proposal, but provided under a seperate purchase.
- Equipment and mechanical system to be stored by Town of Erie until installation.
- Estimate does not include civil drawings and permitting (purchased under a seperate order).
- Estimate does not include costs for incidental pipe & fittings, nor incidental conduit & wire.
- Health department submission and associated fee's are not included in this estimate.
- Domestic water supply includes solenoid and time clock to set hours of operation if so desired.
- Water heaters available for additional costs.
- All ground spray features are imbed and installed prior to concrete being poured.
- SS represents stainless steel material. Additional fees may apply for products to be powdercoated.
- Additional notes listed on drawing 1154291-01-01 Coal Creek Layout by Aquatix apply.
- Estimate does not include shade structures, site amenities, landscaping, lighting or fencing.
- Upon arrival of the equipment and mechanicals (excluding the vault/underground water reservoir) final payment will be due to Rocky Mountain Recreation, Inc. While the vault can ship in 2022 based on project schedule it shall not impact or delay final payment.